

RENEWABLE ENERGY FOR RURAL ELECTRIFICATION: LESSONS FROM MALAWI

Lameck K. Nkhonjera
University of Malawi–The Polytechnic

AFRETEP 3rd REGIONAL WORKSHOP
Cape Town South Africa, 20–24 February 2012

HIGHLIGHTS

SIZE

118,484 km² (20% Water)

POPULATION

13 Million (86% Rural)

GDP/capita

US\$337

Electrification

7.6% (1% Rural)

ENERGY RESOURCE

Biomass, coal, hydro, solar, wind



RURAL ELECTRIFICATION INITIATIVES

INTERVENTION

```
graph TD; INTERVENTION --> MAREP; INTERVENTION --> BARREM; MAREP --> MAREP_List["1. Grid extension<br/>2. 4.5MW Hydro<br/>3. Solar villages (20.1 KW)"]; BARREM --> BARREM_List["1. PV in sch. & HC<br/>2. SHS<br/>3. Water Pumping"];
```

MAREP

1. Grid extension
2. 4.5MW Hydro
3. Solar villages (20.1 KW)

BARREM

1. PV in sch. & HC
2. SHS
3. Water Pumping

| System Type | No systems | Average Wp | Total Wp |
|--|-------------------|-------------------|-----------------|
| Households | 4000 | 20 | 80000 |
| Institutions (not stated whether schools or health or other) | 178 | 75 | 13350 |
| Health Centres (lighting) | 150 | 75 | 11250 |
| Health Centres (vaccine) | 130 | 140 | 18200 |
| Beverage Coolers | 11 | 375 | 4125 |
| Water pumps | 113 | 200 | 22600 |
| Radio communication | 150 | 30 | 4500 |
| Total | 4732 | | 154025 |

RURAL ELECTRIFICATION INITIATIVES

INTERVENTION

MAREP

1. Grid extension
2. 4.5MW Hydro
3. Solar villages (20.1 KW)

BARREM


1. PV in sch. & HC
2. SHS
3. Water Pumping

KAVUZI

10 KW saving a community of 80 households

OTHERS


1. PV in sch, HC
2. PV homes
3. PV-wind Hybrid



Universities

TRAINING

**Barefoot
Project**





Mounting PV module
on a roof

Preparations for installation




Universities

TRAINING


**Barefoot
Project**

**User Training
(on site)**




LESSONS


1. Solar and micro hydro electricity are proved viable.
2. Productive time, livelihood, education and flow of information are improved in the project areas
3. Lack of good policies to promote technology uptake



LESSONS

2. Financing mechanism unsatisfactory
 3. Poor resource assessment
 4. Increased unprofessional installations–poor system performance
 5. Poor system management by end users
 6. Influx of low standard RE equipment
 7. Lack of after sale services
 8. Theft
- 

CONCLUSIONS

- Solar PV remains the most used alternative energy for rural electrification in Malawi
 - Rural electrification interventions have not substantially increased level of rural electrification
 - Many challenges still need to be addressed in order to have effective rural electrification through renewable energies.
- 

I WELCOME YOUR COMMENTS